

**DELHI TRANSPORT CORPORATION
OFFICE OF THE MANAGTER (C) PC-III
I. P.ESTATE: HQ. NEW DELHI.**

No.

Dated:

Limited Tender/Quotation.

To,

M/s _____

Sub: - Providing & Fixing Interlocking Tile flooring in yard & Kota stone flooring in open Terrace & sun shed at BBM-I officer flat.

The **percentage rates quotations** are invited by this office for the execution of the work: -

“Providing & Fixing Interlocking Tile flooring in yard & Kota stone flooring in Open Terrace & sun shed at BBM-I officer flat.”
as per schedule of quantities enclosed.

The offer shall be received in the tender cell, room No.-207 at DTC Hqtr., I.P. Estate New Delhi-110002 before 12.00 hrs. on dated 01.12.2009 and shall be opened at 15.00 hrs. on dated 01.12.2009.

You are requested to kindly send your offer before due date and time.

Terms & Conditions.

- (i) The work shall be executed as per CPWD specification 1996 Vol.- I to VI with correction slips issued up to the date and as per direction of Engineer –in –charge.
- (ii) The contractor shall take all safety measures for satisfactory completion of the work at his own cost. And he shall be completely responsible for any mishap that may occur during execution of the work.
- (iii) No T & P will be provided by the DTC.
- (iv) All the taxes like TDS @ 2.266%, ESIC @ 6.5% (on labour), CESS @ 1% & WC Tax @ 4% etc. will be deducted as per government rule.
- (v) The percentage rates quoted by the contractor includes cost of royalty, octroi, local taxes, cartage, labour, material etc. and all other inputs involved for satisfactory execution of the work/items.
- (vi) The contractor shall make his own arrangement for filtered & unfiltered water, for use in construction and for his labour.
- (vii) The time allowed for the execution of the work shall be **30 days.**

Thanking you.

Encl: - Schedule of items.

Yours faithfully,

(O. P. Sharma)
Manager (Civil) PC-III

Schedule of Quantity

Name of Work: -Providing & Fixing Interlocking Tile flooring in yard & Kota stone flooring in Open Terrace & sun shed at BBM-I officer flat.

S. No.	Discription of Item	QTY	Unit	Rate (Rs.)	Amount. (Rs.)
1	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction and of approved size and design/ shape laid in required colour and pattern over and including 50mm thick compacted bed of course sand, filling the joints with coarse sand etc. all complete as per the direction of Engineer-in-charge.	130.00	sqm	345.45	44908.50
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. 1:3:6 or richer mix	4.00	cum	368.45	1473.80
3	Making chases up to 7.5x7.5 cm in walls including making good and finishing with matching surface after housing G.I. pipe etc.	20.00	meter	36.65	733.00
4	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick.	65.00	sqm	694.40	45136.00
Total Amount =					92252.00

Manager (C) PC-III

S. O. (C)